App. F. IX—4

Previous References.

JTB 18·53-38

(1955·56) JTB.

Later References.

File No. 14-S5-

Serial Nos. 21, 58.

MYSORE GOVERNMENT SECRETARIAT

Serial Nos. 2

21

Part B for Feb 1956

SUBJECT

Revised estimate for Constructing 16 Model houses behind All India Radio, Mysore

WD 0249—GPB—25,000—16-9-55

(14505) 10.2.56.

The Chairman, M.C.B.

" C.S.A.

" C.R.

Sanctions

C. Vasavi

M. G. S. APP. F. III—11

MYSORE GOVERNMENT SECRETARIAT.

NOTES. File No.

FILE HEADING.

FROM The Chairman, city Impt Bd Mysore

No. D2. C. 261/53-4 Dated 23. 8. 55 Received 1-9-55.

Diary No. 3760 | Enclos. Records Spare copies | Serial No:

BRIEF ABSTRACT OF LETTER

Revised estimate for constructing 16 model houses behind All India Radio Mysore

NOTES AND ORDERS.

Submitted

1) Collection leaving to the issue of GO No. DI 3130-32/HHB 18-53-31 dated 9/54 is pmnp with DNO 7413/2590/55-6 Ml. This file bearing DNO 2590 Ml has been sent unofficially to the Chief Engineer for remarks on 18. 8. 55.

2) The Chairman city Impt Bd Mysore requests Sanction to the revised estimate for Rs. 80,480/- as against the original estimate for Rs 74,400/-

3) The file may be referred to the CE for remarks. forwarded thereon as pmnp for Govt approval

Notes—First Sheet R 6/9/55

WC 04864—GPB—20,000—22-1-54

Revised estimate for Constructing 16 model

2 houses behind All India Radio, Mysore III

File No. 3760 of 195 — Mysore Government Secretariat

U.O.No. 16 / RB 13-9 55

4 Forwarded to the Chief Engineer of Mysore Bangalore for remarks and early return

Sri F.R.S. Sup't — Hanumanthappa 7/9

for Secy Edn & I.S.G. Depts

B.W. — Rb 7/9 — Mr 7/9

Signed 8/12/55 C.E — Rb 13/9 — Draft put 13.10.55

Mr 8/10/55

The office file is not made available by the Cashier. — Refer to No. & Date — Mr 22/10/55

Labour Officials Forms — Mr 22/10/55 — Replied on Mr 10/11/55

G 22.10.55

R.B. 7594 / one file

31-10-55

Not Registered RB (159) M

U.O.No. 8095 /RB-55-56 dated, 9th December 1955.

5) Retransmitted. 8 vol. one U.O. file

6) The estimate is scrutinised to Rs. 80480/- only.

10 DEC 1955

R. Madhavan 8/12

(R. MADHAVAN)
Deputy Chief Engineer.

Secretary to Government,
Education & I.S.G. Departments,
Bangalore.

G 7.12.55

IS/7-12-55.

7) Submitted:- In G.O. No. D 13/20-32/STR 18-53, 30 (Copy of Circular Proc.) we have requested the Chairman to send a supplementary estimate for providing water supply and sanitary fittings to the Blocks. The Chairman has returned the original estimate for Rs 74,600/- (Sanctioned in G.O. read above) along with the revised estimate and requests that the revised estimate for Rs 80,480/- may be sanctioned

3760 M56975

Revised estimate for 200 meeting 16 Model hours 3
Relay All India Radio Mysore

×/para 6

8) The CE has scrutinised the estimate for Rs 80,480/- for which the revised estimate of Rs 80,480/- may be sanctioned in the circumstances explained by the Chairman of S.T.B.

L 29/12 ME 22/12

(9) The Estimate may be sanctioned for Rs 80,480/- as Scrutinised by the Deputy Chief Engineer

Secy (Com & Lab)

(10) Revised estimate for Rs 80,480 may be sd.

29/12/55

Minister (Lab) Hon H. Sec

(11) 2/12

(12) 3.4.56

(13) 18/1/57

Libro (14) Sanction is accorded to the revised estimate

(15)

L 28/1 Mes 27/1

1737
26 DEC 1955
GOVERNMENT OF MYSORE
FINANCIAL SECRETARY
GC
31 DEC 1955
U. O. No. 11684
15164
19 JAN
No 4691

3260 Nos ∫ 6975

Revised estimate for Construction Material
Stores Cabinet Air India Radio, Mysore

4

Revised estimate for Rs 80,480/- as
performed by the Deputy CE is
Sanctioned - original estimate
for Rs 74,400/- is Sanctioned's
Cancelled

L 14505-07 / 4003 14-15-5855 2/58

No. D2.C.261/53-4

Encl. One file

OFFICE OF THE CHAIRMAN,
CITY IMPROVEMENT TRUST BOARD,
POST BOX NO. 55, MYSORE.

Dated 23rd August *1955*.

FROM

SRI S. LINGANNA.
Chairman, City Improvement Trust Board,
MYSORE.

To

.....Sri B.M.Krishnan, B.A., I.A.S.,
Secretary to the Government of Mysore.
Education & - *Local Self-Government* ~~&Planning~~ *Departments,*
BANGALORE.

SIR,

Subject : Revised estimate for constructing 16 model houses behind All India Radio, Mysore.

In forwarding herewith a revised estimate for Rs.80,480/- for the above work, I write to state as follows:-

The estimate for Rs.74,400/- was sanctioned in G.O.No.L.13130-32/ ITB.18-53-38 dated 9-1-1954 with the observation that a supplemental estimate may be got up for ~~the~~ providing water supply and sanitary fittings, electric lights etc., and sent to Government and the cost thereof be included in the cost of the houses. It was also observed that R.C.C.lintles for verandah and cement plastering for the interior surfaces of the lavatory, bath and kitchen may be provided for. Accordingly, the estimate has now been got up providing for all the items of work as per actual execution. The houses constructed have been provided with underground drainage, water supply and electric lights and also with copper boilers in the bath rooms.

The first observation in para 2(a) of the preamble of the Government Order cited above, refers to provision of only 4 doors as against 5 doors shown in the drawing. In order to minimise the cost, one door leading from the Hall to the rear is only left as a door opening, and hence no provision for a door and shutter has been made in the estimate. The total cost of each house as per actuals comes to Rs.5030/- excluding the site value. The total amount of the revised estimate for the 16 houses thus comes to Rs.80,480/-

The rates provided in the estimate are in accordance with the

P.T.O.

V

accepted tender rate and for non-tendered items, datas are furnished wherever necessary. I request you kindly to obtain and communicate early sanction of Government to the Revised estimate.

In this connection, it may be stated that out of the 16 houses, 13 have already been disposed off, and the sale value has been fixed including the cost of site at Rs.4-8-0 per syd, and establishment and supervision charges at Rs.560/- per house.

The original estimate for Rs.74,400/- is herewith enclosed for cancellation; The other connected records accompany.

Yours faithfully,

S. Linganna 23/8/87

(S.Linganna)
Chairman.

DVS)

MYSORE CITY IMPROVEMENT TRUST BOARD.

NAME OF WORK: Constructing model houses behind All India Radio, Mysore. 3

NAME OF CONTRACTOR: Sri S.Ramaswamy,

AMOUNT OF ESTIMATE Rs. 4,069/- AMOUNT OF TENDER Rs. 3,941/-

Sl. No.	Particulars	Unit	Rate	In words
1.	Earth work excavation in H.G.soil for foundation and filling in basement including watering and tamping.	Cyd.	0-10-0	As.Ten only.
2.	Laying quartz jelly concrete in lime mortar 1:3(1" to 1½" size metal).	Cft.	0- 6-6	As.Six and Ps.Six only.
3.	Size stone in clay with bond stone at 6' apart (close grained bluish stones).	Cft.	0- 9-9	As.Nine and Ps.Nine only.
4.	Laying cement concrete 1:3:6 with granite jelly ½" to ¾" in size over basement	Cft.	1- 0-0	Rs.One only.
5.	B.B.in clay for superstructure.	Cft.	0- 8-3	As.Eight and Rs.Three only.
6.	-Do- in lime mortar for sides of doors and windows.	"	0-10-3	As.Ten and Ps.Three only.
7.	-Do- in cement mortar 1:6.	"	0-13-0	As.Thirteen only
8.	R.C.C.Circular pillars with 1½% reinforcement with cups and bases as per design including plastering alround.	"	4- 0-0	Rs.Four only.
9.	Laying cement concrete 1:3:6 with granite jelly ½" to ¾" thick in size for wall plate alround.	"	1- 0-0	Rs.One only.
10.	Providing and fixing D.B:slab 3" to 4" thick cut and fixed in mortar for lintlesover doors and windows.	Sft.	0-13-0	As.Thirteen only.
11.	Providing and fixing T.W.doors 3" x 4" frame work, 1½" thick panelled shutters with necessary iron fittings and 2 coats of Mysore Lac Factory green painting etc.,complete.	Sft.	4- 0-0	Rs.Four only.
12.	R.C.C.lintles for verandah as per design.	Cft.	5- 0-0	Rs.Five only.
13.	Providing and fixing T.W.windows 3" x 4" frame work 1" thick panelled shutters with ⅜" iron bars and iron fittings with 2 coats of Lac Factory green paintings etc., complete.	"	5- 0-0	Rs.Five only.
14.	Providing and fixing 1" thick jungle wood plank for ~~shut~~ Shift	"	0-10-0	As.Ten only.
15.	Providing and fixing jungle wood planks shelf 1" thick fixed to T.W.Brakets 3" x 4"x2½" including 2 coats of painting etc., complete.	"	1- 6-0	Rs.One and As.Six only.
16.	Providing and fixing R.C.C.ventillators as per design.	"	1- 8-0	Rs.One and As.Eight only.
17.	Roofing with R.C.C.5" thick slab to take a super load of 140-150 lbs.with necessary reinforcements as per specifications including weather proof coating and top and bottom plastered etc., complete.	Sqr.	150- 0-0	Rs.One hundred and Fifty only
18.	- do - 3" thick for verandah.	"	120 -0-0	Rs.One hundred and Twenty onl
19.	Flooring with 1½" cement concrete with granite			

P.T.O.

	granite jelly ¼" to ⅜" in size on a bed of 3" lime concrete with broken quartz jelly 1" to 1½" in size and ½" thick plastering 1:3 with toping of red cement ⅛" thick finished etc., complete.	Sqr.	36- 0-0	Rs.Thirty-six only.
20.	R.C.C.Chejja 2½" thick with necessary reinformement including top and bottom plastered (visible portion only measured).	Sft.	2- 0-0	Rs.Two only.
21.	Plain prapet wall 9" thick ½" high including plastering.etc., complete.	Rft.	0- 6-0	As.Six only.
22.	Band cornice as per design complete.	"	0- 2-0	As.Two only.
23.	Lixe mortar plastering ½" thick including rounding of corners complete.	Sqr.	6- 0-0	Rs.Six only.
24.	White and colour washing 2 coats.		0- 8-0	As.Eight only
25.	Providing and fixing mortar and pestle.	Each	10- 0-0	Rs.Ten only.
26.	Providing and fixing zinc sheet door for latrine.	Sft.	1- 8-0	Rs.One and As.Eight only.
27.	Providing and fixing zinc sheet rain water down pipes of 3" dia. with bends complete.	Rft.	1- 4-0	Rs.One and As.Four only.
28.	Constructing compound wall 9" thick 4½' high on a foundation of size stone in mud 1½' x 1' on a bed of lime concrete 6" thick including coping at top and lime plastering etc., complete as per design.		3- 0-0	Rs.Three only.
29.	Providing and fixing T.W.gates 3'x3' as per design with iron fixtures etc	Sft.	2- 0-0	Rs.Two only
30.	Constructing chimmney in bath and kitchen as per approved design.	Each.	15- 0-0	Rs.Fifteen only.
31.	Cement mortar plastering 1:3 half inch thick	Sqr.	9- 0-0	Rs.Nine and As.Nine only
32.	Cement pointing 1:3 including racking the joints 1" deep.	"	5- 0-0	Rs.Five only.

I do hereby agree to execute the above work at the rates quoted by me as above.

Sd/ S.Ramaswamy,
Contractor.

"Copy"

K.V.Rajanarayanan

For Chairman.

JV)

MYSORE CITY IMPROVEMENT TRUST BOARD.

Estimate for .....Constructing model houses behind All India Radio in Yadavagiri Extension, Mysore.

WD 9—GBPM—5,000—19-4-50

Sl. No.	Particulars	No.	Dimensions L.	B.	D.	Contents	Unit	Rate Rs.	a.	p.	Cost
1.	Earth work excavation in H.G.soil for foundation and filling in basement including watering and tamping		Sanctioned 82/9-1-53			18:53-3-8	V.Qc.	G.O.			d. 13/30 Dated 9.1.52
	main building alround.	1	88¼	2	2½	441					
	Bath (three sides)	1	23⅜	2	2½	117					
	Wall between kitchen block and hall.	1	13⅛	2	2½	66					
	Cross wall between dining and bed room.	1	9⅛	2	1	18					
	Verandha retaining wall	1	14⅛	1½	1	21					
	Retaining wall infront of bath and latrine wall	1	8⅛	1½	1	12					
		1	7	1½	1	11					
	Extra for steps &c. &c.					116					
			Total....			802	Cft.				
					or	30	Cyd.	-	10	-	19
2.	Quartz jelly concrete in lime mortar 1" to 1½" in bunje										
	main bulding alround.	1	88¼	2	½	88					
	Bath (three sides) wall between kitchen block and hall.	1	23⅜	2	½	23					
		1	13⅛	2	½	13					
	Cross-wall between dining and bed room.	1	9⅛	2	½	9					
	Verandah retaining wall	1	14⅛	1½	½	11					
	- do - infront of bath,	1	8⅛	1½	½	6					
	Latrine wall	1	7	1½	½	5					
	Extra for steps &c. &c.					15					
			Total....			170	Cft.	-	7	-	74
3.	Size stone in mud for foundation and basement main building alround, C.O	1	88¼	1½	2¼	298					

	Bath (three sides)	1	23 7/8	1 1/2	2 1/4	81				
	Wall between kitchen block and hall.	1	13 3/8	1 1/2	2 1/4	46				
	Cross wall between dining and bed room.	1	9 5/8	1 1/2	1 1/2	22				
	Latrine wall.	1	7 1/4	1 1/2	1	12 / 41				
			Total.....			459 / 570	Cft.	-	10	~~288~~ 313
4	(a) Cement concrete (1:3:6) over basement including mixing laying and tamping using granite jelly 1/2" to 3/4".	1	88 1/4	1 1/2	1/4	33				
		1	23 7/8	1 1/2	1/4	9				
		1	13 3/8	1 1/2	1/4	5				
		1	9 5/8	1 1/2	1/4	4				
	Verandah retaining wall front	1	14 5/8	1 1/8	1/4	4				
	- do - Rear	1	8 5/8	1 1/8	1/4	3				
			Total.....			58	Cft.	1	-	- 58
	(b) Cement mortar plastering 1:3) 1/2" thick exposed face of above concrete (item No.4 a) and retaining wall of verandah front and rear.	(L.S. (Details during execution				125	Sqr.	9	8	- 12
5.	Cement mortar pointing (1:3) including raking jointing 1" deep alround.	1	90 7/8		1 1/4	114				
	Extra for step etc. ~~L.S.~~	1	23 7/8	-	1 1/4	30				
			Total.....			144	Sft.			
					or	1.~~66~~44	Sqr.	5	-	-
6.	Burnt brick in mud superstructure main building alround.	1	88 1/4	1 1/8	10	992				
	Bath (three sides)	1	24 1/4	1 1/8	10	273				
	Wall between kitchen block and hall.	1	14	1 1/8	10	158				
	Cross wall dining and bed room.	1	10	3/4	10	75				
	Latrine.	1	8 1/8	3/4	6	37				

WD 9—GBPM—5,000—19-4-5

Sl. No.	Particulars	No.	Dimensions L.	B.	D.	Contents	Unit	Rate Rs.	a.	p.	Cost
	Extra for raising compound in latrine portion.	1	8⅛	¾	1½	10					
	Verandah retaining wall front.	1	15	1⅛	1½	25					
	- do - Rear.	1	9	1⅛	1½	16					
		Total.....				1586	Cft.				
	DEDUCT FOR:										
	Doors	4	3	1⅛	6½	88					
	Door opening	2	3	1⅛	6½	44					
	Windows big.	2	4	1⅛	3¾	34					
	- do - small	4	3	1⅛	3¾	50					
	Ventilator	1	2½	1⅛	1½	4					
	Lintels over doors.	4	4½	1⅛	¼	5					
	Opening	2	4½	1⅛	¼	2					
	Windows big.	2	5½	1⅛	¼	3					
	- do - small	4	4½	1⅛	¼	5					
	Wall shelves	2	3	¾	4½	20					
		1	3	¾	4½	10					
	Lintels	2	4½	1⅛	¼	3					
		1	3		¼	1					
	Latrine door	1	2	¾	6	9					
	Ventilator	1	4	1⅛	¼	1					
	Burnt brick in lime mortar for sides of doors, windows etc.										
	Doors sides	4x2	¾	1⅛	6½	44					
	Opening	2x2	¾	1⅛	6½	22					
	Windows big.	2x2	¾	1⅛	3¾	13					
	do - small	4x2	¾	1⅛	3¾	25					
	Sides of windows Big.	2	5½	1⅛	½	6					
	- do - small	4x2	4½	1⅛	½	20					
	Wall shelves	2x2	¾	1⅛	4½	15					
		1x2	¾	¾	4½	5					
		Total				429½	Cft.				

		B.F.								
	Balance quantity of B.B. in mud in Cft. 1586-~~429~~ 462 =									
						1124	Cft.	-	8	6
7.	Burnt brick in lime mortar as per deduction in item No.6.	(Qty. marked 'A' above)				161 ~~150~~	"	-	10	6
8.	Burnt brick in cement mortar (1:6) partition wall between kitchen and dining.	1	7	⅜	7	19	"	-	13	-
9.	Rein-forced cement concrete pillar (1:2:4) with granite jelly ½" to ¼" with necessary rainfocement as per design including plastering alround.	¼x7	22 x ½x8			4 ~~44~~	"	4	-	-
10.	Cement concrete with granite jelly ½" to ¾" (1:3:6) bed slab over walls main building alround.	1	88¼	1⅛	¼	25				
	Bath room (3 sides)	1	24¼	1⅛	¼	7				
	Wall between kitchen block and hall.	1	14	1⅛	¼	4				
			Total.....			36	Cft.	1	-	-
11.	Providing and fixing B.S. slabs 3" to 4" thick (D.B.Slabs) including rough dressing.									
	Lintels over doors	4	4½	1⅛	-	20¼				
	- do - Openings.	2	4½	1⅛	-	10⅛				
	- do - windows big.	2	5½	1⅛	-	12⅜				
	- do - small	4	4½	1⅛	-	20¼				
		2	4½	1⅛	-	10⅛				
	Wall shelves.	1	4½	¾	-	3⅜				
	Ventilator	1	4	1⅛	-	4½				
			Total.....			81 87	Sft.	-	13	-
12.	T.".doors 3" x 4" frames 1¼" thick panelled shutters with necessary iron fixtures like pad lock things screws tower bolts, stoppers etc., including 2 coats of Lac Factory green painting. Ed. complete	1	15		½	10	Nr	5	-	50
		4	3	-	6½	78	"	4		312

MYSORE CITY IMPROVEMENT TRUST BOARD.

Extimate for .....

WD 9—GBPM—5,000—19-4-50

Sl. No.	Particulars	No.	Dimensions L.	B.	D.	Contents	Unit	Rate Rs.	a.	p.	Cost
											17'8
13.	T.W. windows 3"x4" frame 1" thick panelled shutters opening out side ⅝" iron bars including necessary iron fixtures like hinges screws stoppers etc., with 2 coats of Lac Factory green painting &c. Comp	2	4		3¾	30					
		4	3		3¾	45					
			Total.			75	Sft.	5	-	-	375
14.	Providing 1" thick jungle wood planks for shelves (two for) each shelf.	2x2	3½	5/6	-	12					
		1x2	3½	¾	-	5¼					
			Total.....			17¼	Sft.	-	12	-	13 4
15	Jungle wood planks shelf 1" thick fixed to T.W.brackets of 3"x4"x2¼" including necessary carpenting work.	2	7	1	-	14	"	1	10	-	23 4
16.	Providing and fixing R.C. ventilator asper design.	1	2½	-	1½	3¾	"	1	8	-	6 4
17	(a) R.C.C.roofing ~~with~~ 5" thick~~ness of slab equal to 1/24 of span (5" thick)~~ with necessary reinforcements, ~~laid to proper slope~~ to take a superload of 150 lbs/sqft including weather coat and ~~top and plastering of~~ ceiling plastering etc complete. Roof Course										
	Bed kitchen and ~~Chimney~~ dining	1	23	12¼	-	282					
	Hall	1	16¼	11⅛	-	181					
	Bath	1	9⅛	8¼	-	75					
			Total...			538	Sft				
					or	5.38	Sqr.	150	-	-	807
	(b) - do - 3" thick for roof of verandah front. c.o	1	10½	7½	-	79					

	Rear	1	5	4		20				
			Total....			99	Sft.			
					or	0.99	Sqrs.	120	-	- 119
18.	Flooring with 3" thick lime concrete 1½x with ~~granite~~ Quartzy Jelly 1" to ½" and ~~jelly~~ 1½" cement concrete with granite jelly ½" to ¾" and ½" ~~th~~ thick cement mortar plastering (1:3) etc., complete.									
	Hall	1	14	10	-	140				
	Kitchen and dining.	1	12	10	-	120				
	Room	1	10	8	-	80				
	Bath	1	9	6	-	54				
	Verandah front	1	7⅞	4⅞	-	38				
	- do - Rear.	1	3⅞	2⅞	-	11				
		Total....				443	Sft.			
					or	4.43	Sqrs.	40	-	- 177
19.	R.C.C.chajja with necessary reinforcement including top and bottom plastered. with fin' 1:2 & all									
	Windows small (1:2 plastered)	4	5	1½	-	30				
	do - big	1	6	1½		9				
		Total....				39	Sft.	2	4	- 88
20.	Plain parapet wall 9" thick and ½' high including plastering. Etc. Complete.	1	115			115	Rft.	-	8	- 58
21.	Band cornice as per design	1	115			115	"	-	3	- 22
22.	Lime mortar plastering ½" thick including rounding of corners and smooth rendering.									
	In side.									
	" Hall alround	1	48	-	10	480				
	" Kitchen and dining.	1	44	-	10	440				
	Bed room	1	36	-	10	360				
	Bath	1	28	-	10	280				

WD 9—GBPM—5,000—19-4-50

Sl. No.	Particulars	No.	Dimensions L.	B.	D.	Contents	Unit	Rate Rs.	a.	p.	Cost
	Latrine	1	7	-	6	42					
	Out side:- alround (Main building)	1	115	-	10½	1208					
	Latrine.	1	8½	-	6	51					
	Partition wall between kitchen and ~~chimney~~ dining.	1x2	7	-	7	98 ~~49~~					
	DEDUCTXN FOR:	1	½	-	7	5 ~~2915~~ 2964					
	Doors	4	3	-	6½	95 ~~78~~					
	Door openings	2	3	-	6½	39					
	Windows big	2	4	-	3¾	30					
	do - small	4	3	-	3¾	45					
	do - ventilator	1	2½	-	1½	4					
	Total lime mortar plastering		Total.....			~~196~~ 216	Sft.				166
	less ~~xxxx~~ deduction in sft.	2964	-211	27.68		27.68	Sqr.	6	-	-	~~166~~
		~~2915~~	-196=	~~2719~~	or	~~27.19~~ 27.48					
23.	Providing and fixing mortar pestle.	1				1 No.	each	10	-	-	10
24.	White and colour washing two coats.	(Quantity as per above item in				27.68 ~~27.35~~	Sqr.	-	8	-	14
25.	Providing and fixing ~~xxxx~~ zinc sheet door for latrine.	1	2	-	6	12	Sft.	1	8	-	18
26.	Providing and fixing rain water down pipes including bend ~~xxxxxxxxxxxx~~ &c. complete	7	3	-	-	21	Rft.	1	8	-	32
27.	Constructing compound wall of 9" thick brick wall 4½ high on foundation of sizestone in mud (1½x1') on bed of lime concrete 6" thick including coping and top and plastering	1	96			96	Rft.	3- ~~2~~	4	-	312

12

			B.F.		1	25					
	(1:3) plaster										
28.	Providing and fixing T work										
	gate 3'x3' as per design with										
	necessary ~~in~~ Iron fixtures.	1	3	3½		10½	Sft.	2	-	-	21
29.	Constructing chimney in bath										
	and kitchen. (as per design)	-	2			2	each	20	-	-	40
30.	Constructing steps infront	(L.S. Details during									50
	and rear.	execution.)									
31.	Levelling ground and forming.					L. S					20
32.	Constructing washing platform										
	drain and ~~other~~ unforeseen works.										~~34~~ 36
	Cost of constructing on model										
	house as per accompanying design.										3940
	- do - site value.										~~4400~~ 460
	Cost of constructing 16 model										R 4400/ 4650
	houses.				46.1 (4400x16)=70400						70400
											74,1

JV) Sanctioned for Rs 74,400 00

15/11/15

Trust Board Engineer.

Scrutinised for Rs. 74,400/-
Rupees Seventy four thousand four hundred only
for Chief Engineer

Sanctioned for Rs 74,400/- only

Secretary to Govt.

6975-

No. D.D2.C.261/53-54.
Encl.

OFFICE OF THE CHAIRMAN,
CITY IMPROVEMENT TRUST BOARD,
POST BOX NO. 55, MYSORE.

FROM

SRI S. LINGANNA,
Chairman, City Improvement Trust Board,
MYSORE.

Dated 19th December 55.

TO

Sri B.M.Krishnan, B.A., I.A.S.,
Secretary to the Government of Mysore.
Education & Local Self-Government Departments,
BANGALORE.

SIR,

Subject: Revised estimate for constructing 16 model houses behind All India Radio, Yadavagiri Extension, Mysore.

I write to invite your kind reference to this office letter of even No. dated 23-8-1955 on the above subject, and to request you kindly to obtain and communicate the sanction of Government to the Revised estimate, at a very early date.

Yours faithfully,

(S.Linganna) 19/12
Chairman.

DVS)

Submitted:- The main file bearing D.No. 3760 etc has been submitted for orders on 4.1.56. The receipt of the main file may be awaited

4/1/56

4/1

M. G. S. App. F VI—G. 2]

15

SUBJECT .....

.....

.....

Diary No. of letter replied to.....

Section STB

Serial No. 14-55

File No. 58

Mysore Government Secretariat

( )

the 195

Proceedings of the Government of Mysore

flag 'R'

Date of issue.....195

Signed by.....

May this be—

(i) printed ?

(ii) treated as a Standing Order ?

(iii) published in the Gazette, English Part ?

(iv) translated ?

(v) placed at the disposal of the Press ?

(vi) published in the Gazette, Kannada Part ?

† May be sent ate

Read (1) G.O.No.L18130-32/STB 1853-3 Dated 9.1.54 according Sanction to the estimate for Rs 7k.400/- for the Construction of 16 House hours behind All India Radio Station Yadavagiri Extension with the observations that Order thereon.—No. ~~Regarding the Chairman MTB to send~~ a Supplemental estimate for providing water Supply and Sanitary fittings to the Bldgs

(2) Letter No Dy.C.261/53-4 Dated 23rd August 1955 from the Chairman MTB forwarding a revised estimate for Rs 80,480/-

16

As per actual execution and

Requesting Sanction to the Revised

Estimate in the Circumstances

Stated Here in

(3) Ho No 8095/RB55-58 dated

9.12.55 from the Deputy Chief Engineer

Returning the estimate duly

Scrutinised for Rs 80,480/-

Order No L 14505-0)

D 10-L-56.

The revised estimate for Rs 80,480

(Rupees Eighty thousand four hundred

Eighty only) as scrutinised by the Dep'ty

CE. is Sanctioned

The original estimate for Rs 74,400/-

Sanctioned in the G.O dated 9.1.54

read above is Cancelled

for Secy Edn Dept.

Dy No Dt Ms.

List of Enclosures.

Copied by

Examined by

The Chairman MTB with the remarks

The Comptroller & Audit Officer

The CE Nagpore Circle

WD 03540—GPB—40,000—13-8-53

17

PROCEEDINGS OF THE GOVERNMENT OF MYSORE.

READ:-

Government Order No.L.13130-32/ITB.18-53-38 dated 9-1-54 according sanction to the estimate for Rs.74,400/- for the construction of 16 model houses behind All India Radio Station, Yadavagiri Extension with the observations that a supplemental estimate for providing water supply and sanitary fittings to the buildings may be sent etc.,

2. Letter No.I.C.C.261/53-54 dated 23-6-1955 from the Chairman City Improvement Trust Board, Mysore, forwarding a revised estimate for Rs.80,480/- as per actual execution and requesting sanction to the revised estimate in the circumstances stated therein.

3. Un-official No.8095/A.S.56-56 dated 9-12-1955 from the Deputy Chief Engineer returning the estimate duly scrutinised for Rs.80,480/-

-:-

ORDER No... 14505-607/STB. 16-12-58

Dated, Bangalore, the 10-2-58.

The revised estimate for Rs.80,480/- (rupees eighty thousand four hundred and eighty only) as scrutinised by the Deputy Chief Engineer is sanctioned.

2. The original estimate for Rs.74,400/- sanctioned in the Government dated 9-1-54 read above is cancelled.

(V.Hanumanthappa)
for Secretary to Government,
Education & L.S.G.Departments.

To

The Chairman, City Improvement Trust Board, Mysore, with records
" Controller, State Accounts Department, Bangalore,
" Chief Engineer of Mysore, Bangalore.

knr-6/7256